MERIDIAN CENTRAL ESTATE - STAGE 40

BROWNS PROPERTY PTY. LTD. CITY OF CASEY

CONSTRUCTION NOTES

SITE MANAGEMENT

- A1. Prior to commencement of works on site, the contractor must ensure that all matters relating to the Occupational Health & Safety Act 2004, including all relevant regulations, have been addressed. In particular, the required notifications must be conveyed to the Victorian Workcover Authority Health & Safety division with respect to trenching operations. Details of the contractors occupational health & safety procedures must be lodged with the superintendent prior to commencement of works.
- A2. All native trees & shrubs to be retained unless road construction necessitates their removal or removal is directed by the engineer. A town planning permit is required for the removal of native trees & / or vegetation. The removal or retention of any existing trees must be in accordance with the approved landscape plan, or else approval will be required from the City of Casey landscape approvals officer.
- A3. Existing dam or watercourses to be excavated to a firm base & backfilled as specified. Consulting engineer to be notified when the dam or watercourses are excavated to a firm base. No filling is to be placed prior to dams being inspected & levels taken. Backfilling is to be carried out to the satisfaction of the Council supervising engineer.
- A4. Prior to commencement of works, the contractor must submit a Site Management Plan (SMP) to the consultant for approval. The contractor must comply with the recommendations of the Environment Protection Authority publication No.275 "Construction techniques for sediment pollution control". Appropriate siltation control is to be maintained throughout the construction & maintenance period of the works.
- A5. Provide temporary safety barrier fence (Farm Fence as per MW Std Dwg 7251/4/203) along extent of outfall drain where the drain is greater than 1.5m in depth & side slopes are steeper than 1 in 3. Safety fence to remain until permanent underground drainage is installed.
- A6. A temporary fence shall be erected & maintained around existing trees, nominated to be retained, at all times during construction. (For fencing details & construction works within the "Tree protection zone" refer to the arboricultural inspection report by XXXXX). DELETE IF NOT REQUIRED
- A7. Contractor to remove existing irrigation & drainage pipes & pits encountered on site. Trenches to be backfilled in accordance with notes C2 & C3.

GENERAL

B1. All works to be carried out in accordance with AS2124-1992 general conditions of contract & the City of Casey current specification & standard drawings & to the satisfaction of the City of Casey works supervisor.

- B2. Council to be notified two (2) clear days prior to commencement of works.
- B3. Before commencement of works on trenches in excess of 1.5m deep, the civil contractors construction supervisor must give notice in writing of such proposals to Worksafe Victoria in accordance with Part 5.1, Division 4 of the Occupational Health & Safety regulations (2007) & undertake safety precautions in trenching operations in accordance with Workcover's code of practice (1988).
- B4. Lots to be graded (1 in 150 min slope) & left clean to the satisfaction of the engineer. Finished levels to be compatible with lots adjoining this stage.
- B5. On completion the contractor is responsible for the removal of all rubbish & spoil from site. No surplus trees, vegetation or other
- B6. Reserves to be free draining & to be left in a condition satisfactory to the City of Casey works supervisor.
- B7. Where works are in the vicinity of existing services these services are to be located & the various authorities notified prior to the commencement of works.
- B8. All TBM's & control points are to be maintained & protected at all times during construction. Should any marks be disturbed, the contractor will immediately notify the consultant to arrange re-instatement at the contractors expense.
- B9. Provide painted paling fence along any boundary common to lots & municipal reserves as per Council Std. Dwg. S-706. Palings to be on the reserve side.
- B10. As constructed plans and electronic asset information in D-Spec and R-Spec format must be submitted to Council prior to practical
- B11. A CCTV report must be provided for all drainage lines prior to issue of practical completion.
- B12. An environmental management plan (EMP) must be submitted to and approved by Council prior to the commencement of any works on site and all works must be carried out in accordance with this EMP.
- B13. A traffic management plan (TMP) must be submitted to, and approved by council prior to the commencement of any works on site and all traffic management must be carried out in accordance with this TMP.
- B14. If any existing substandard filling is encountered on the site it must be removed and replaced with approved fill material properly compacted to council requirements. A geo-technical report must be submitted showing detail of depth, type of material and density
- B15. Temporary crushed rock turn around areas must be maintained in a safe and sound condition so that vehicles area able to use them at all times.

ROADWORKS

- C1. 100ø agricultural pipe drains (MPA standard drawing EDCM 202) to be placed behind all kerb & channel & buffer pitchers & where directed by the engineer.
- C2. Filling in all properties & road reserves is to be carried out using approved clay fill. Top soil & all vegetable matter to be stripped from site prior to filling. All filling to be carried out in accordance with AS3798-2007 and the geotechnical report. Level 1 inspection

- and testing to be carried out in accordance with AS3798-2007 Section 8.2. A fill report must be submitted to the Consultant, showing from a NATA registered soil testing laboratory.
- C3. Importing Fill:- All imported fill must be tested by a NATA approved laboratory to ensure it is suitable for use on site, & any contaminates are within accepted levels. Under no circumstances should fill material enter or leave the site without the permissior of the supervising engineer & Council works supervisor, prior to it being appropriately tested. All vehicles transporting fill material to & from the site must have appropriate measures in place to ensure that material does not get onto roads & into stormwater systems & natural waterways.
- C4. Batters to be 1 in 5 for fill & 1 in 3 for cut unless noted otherwise.
- C5. Cut batters are to be grassed & mulched with a mixture of chopped grass, straw & bitumen emulsion.
- C6. Where cut batters exceed 700mm an additional 300mm berm shall be formed behind footpath
- C7. Access ramps are to be constructed where cut batters exceed 1.0m. They are to be graded 1 in 10 for the first 2.5m from the back of path & then at a maximum of 1 in 4 to natural surface.
- C8. The water conduit offset from the lot boundary is given on the water reticulation plan. The contractor must construct conduits to accord with the given offset & ensure that the concreter marks the kerb & footpath exactly above the conduit.
- C9. Irrigation conduits are to be DN100 DWV PVC installed beneath the pavement and/or capping layer, if present. Locations are to be marked using a green dot spray painted on the top of kerb.
- C10. All footpaths are to be 125mm thick 25MPa concrete with SL72 mesh centrally located in accordance with the MPA standard drawing EDCM 401
- C11. NBN Co to be notified seven (7) days prior to concrete works being placed.
- C12. Electrical distribution pits within footpaths are to be a minimum of 300mm within the edge of the path. Concrete is to be placed around distribution pits to a minimum depth of 200mm.
- C13. All street signs to be constructed & erected to current City of Casey standards including logo. Court street names are to show
- C14. Traffic control signs, markings & delineators to be installed in accordance with AS1742.2. All line marking is to be long life road marking, with longitudinal lines in thermoplastic & transverse markings in cold applied.
- C15. Driveways to be constructed in accordance with the MPA standard drawings EDCM 501 & EDCM 502. Single driveways to be a minimum 3.5m wide & to be offset 0.75m from side boundary or easement unless otherwise shown.
- C16. Kerb transition to take place in the minor street over a 2.0m length from either the tangent point or TP pit.
- C16. Kerb transition to take place in the minor street over a 2.0m length from either the tangent point or TP pi
- C17. Existing road works to be reconstructed as required to provide, without discontinuity, a connection in accordance with design levels & grades.
- C18. Provide 2.5m wide shared footpath through reserves as shown on a curvilinear alignment to the satisfaction of the engineer.
- C19. Tactile ground surface indicators (TGSI) are to be installed at all pram crossings & pedestrian cross points in accordance with

DRAINAGE

D1. Drainage & pits to be set out from offsets shown rather than from centreline pipe chainages.

AS1428.4: 2002 & MPA standard drawing EDCM 403.

- D2. Lightweight fibreglass type pit lids are required for all drainage pits & all grates for pits are to be Class D, to comply with AS3996 unless otherwise shown. All drainage works are to be constructed to council specifications.
- D3. All pipes up to and including 750mm in diameter shall be rubber ring jointed (RRJ). Pipes above this size may be flush jointed with external sealing bands. For pipes greater than 900mm and changes in direction between 2 connecting pipes exceeding 10° construct segmented curves using splayed pipes with bandage joints, having deflections within the manufacturer's specification.
- O4. All pipes to be Class '2' R.C. unless noted otherwise. PVC pipes to be Class SH unless specified.
- D5. Pipe trenches beneath the road pavement, footpath or within 150mm of the kerb & channel to be backfilled with 20mm Class 3 FCR in 150mm layers.
- D6. Property inlets to be constructed as per MPA standard drawing EDCM 701 EDCM 704.
- D7. All proposed drainage stubs to be blanked off at end of pipe with timber planks to the satisfaction of the supervising engineer.

PAVEMENT

E1. Modification of the pavement requires approval by the City of Casey works supervisor.

DRAWING No.	TITLE	REVISION
1801767-40-001	COVER SHEET	А
1801767-40-002	TYPICAL ROAD CROSS SECTIONS AND PAVEMENT MAKEUP	А
1801767-40-003	RETAINING WALL DETAILS AND GENERAL DETAILS	А
1801767-40-010	LAYOUT PLAN (SHEET 1 OF 2)	А
1801767-40-011	LAYOUT PLAN (SHEET 2 OF 2)	А
1801767-40-100	ROAD LONGITUDINAL SECTIONS AWEIL LANE AND BERRENDA STREET	А
1801767-40-101	ROAD LONGITUDINAL SECTIONS KHILLARI CIRCUIT (SHEET 1 OF 2)	А
1801767-40-102	ROAD LONGITUDINAL SECTIONS KHILLARI CIRCUIT (SHEET 2 OF 2)	А
1801767-40-200	ROAD CROSS SECTIONS AWEIL LANE AND BERRENDA STREET	А
1801767-40-201	ROAD CROSS SECTIONS BERRENDA STREET	А
1801767-40-202	ROAD CROSS SECTIONS KHILLARI CIRCUIT (SHEET 1 OF 2)	А
1801767-40-203	ROAD CROSS SECTIONS KHILLARI CIRCUIT (SHEET 2 OF 2)	А
1801767-40-300	INTERSECTION DETAILS	А
1801767-40-350	SIGNAGE & LINE MARKING PLANS	А
1801767-40-400	DRAINAGE LONGITUDINAL SECTIONS (SHEET 1 OF 2)	А
1801767-40-401	DRAINAGE LONGITUDINAL SECTIONS (SHEET 2 OF 2)	А
1801767-40-402	PIT SCHEDULE	A


Survey Origin:

Coordinates are on a local plane datum based upon MGA2020 Zone 55 bearings and truncated MGA2020 Zone 55 co-ordinates at PM77. Heights are to AHD vide Permanent Mark PM 56 (Cranbourne) RL 26.71 Bearing Datum is MGA2020 Zone 55 which has been derived by our GPSnet Survey.

Plane Grid Coordinates to MGA2020 Zone 55 Grid Coordinates Conversion.

(PLANE SHIFT) Add + 35 Add +5,78 (APPLY SCALE FACTOR) Scale by 0.99

Add + 353,823.586 to Eastings
Add +5,780,840.520 to Northings
Scale by 0.999846 at point PM77



NOT TO SCALE
MELWAY REF: 135 F4

ISSUED FOR CONSTRUCTION

© COPYRIGHT All rights reserved
Beveridge Williams & Co. Pty Ltd has granted a licence to the principle to use this document for its intended purpose.
No unauthorised copying is permitted

A ISSUED FOR CONSTRUCTION

21.12.22 C.D M.F

REV DESCRIPTION

DATE DRN. APP. REV

DESCRIPTION

DATE DRN. APP. REV

DESCRIPTION

DATE DRN. APP. REV

DESCRIPTION

DATE DRN. APP. REV






Designed C.DAWSON
Date 28.09.2022

Drawn L.SUTHERLAND


Approved M.FELICIANO
Date 18.11.2022


PS904418





Project Details	MERIDIAN CENTRAL ESTATE STAGE 40 CITY OF CASEY
Drawing Title	COVER SHEET


K:\Jobs Data\1801767 - Meridian_Eng\Stage 40\Drawings\1801767-40-001-COV.dwg











ISSUED FOR CONSTRUCTION

© COP	© COPYRIGHT All rights reserved									_
Beverido	Beveridge Williams & Co. Pty Ltd has granted a licence to the principle to use this document for its intended purpose. No unauthorised copying is permitted									
No unauthorised copying is permitted										
Α	ISSUED FOR CONSTRUCTION	21.12.22	C.D	M.F						
REV	DESCRIPTION	DATE	DRN.	APP.	REV	DESCRIPTION	DATE	DRN.	APP.	





Designed Date	C.DAWSON 28.09.2022	
Drawn	L.SUTHERLAND	
Approved Date	M.FELICIANO 18.11.2022	

PS Number PS904418Y




www.beveridgewilliams.com.au

Project Details	MERIDIAN CENTRAL ESTATE
	STAGE 40
	CITY OF CASEY

wing	TYPICAL ROAD CROSS SECTIONS
	AND PAVEMENT MAKEUP

Sheet	02 of	17	
Scale			
AS SHOV	٧N		
Project Ref	Stage No	Drawing No	Rev
1801767	40	002	Α
	Scale AS SHO\ Project Ref	Scale AS SHOWN Project Ref Stage No	AS SHOWN Project Ref Stage No Drawing No




MASS ROCK RETAINING WALL SCHEDULE						
MAX WALL HEIGHT-H(mm) FOUNDING DEPTH-D(mm) BASE WIDTH - B(mm) FRONT FACE SETBACK-S (mm) WIDTH-C(mm)						
400	400	450	15	300		
500	400	500	15	300		
600	400	500	30	300		
800	400	600	30	300		
1000	400	700	30	300		

RETAINING WALL NOTE R.1

a. WHERE FOOTPATH ABUTS RETAINING WALL CONTINUE CONCRETE UP TO BASE OF RETAINING WALL.

FOOTING NOTE F.2.


- a. TOE OF WALL SHALL PENETRATE THROUGH ANY FILL MATERIAL & THE NATURAL SILT SOILS TO BE FOUNDED AT LEAST 100mm INTO THIS UNDERLYING NATURAL STILL CLAY OR WEATHERED ROCK.
- ALL EXCAVATIONS SHALL HAVE FOUNDING DEPTHS AND BEARING CAPACITY APPROVED BY THE ENGINEER OR BUILDING SURVEYOR
- BEFORE CONCRETE IS PLACED. FOOTING EXCAVATIONS WHICH ARE DEEPEND TO PENETRATE THROUGH UNSUITABLE SOILS SHALL BE BACKFILLED UP TO UNDERSIDE OF FOOTINGS
- WITH 15 MPa BLINDING CONCRETE. b. ALL EXCAVATION FOUNDING SURFACES SHALL BE LEVEL (NOT INCLINED) CLEAN CUT & FREE OF MUD OR WATER.
- c. ALL SEEPAGE INFLOW SHALL BE REMOVED BEFORE PLACEMENT OF CONCRETE.
- d. FOOTINGS SHALL BE FOUNDED IN STIFF NATURAL CLAY HAVING A SAFE BEARING CAPACITY OF 150KPa.




NOTES


1. REFER TO EDCM 502 FOR FURTHER DETAILS 8.0m DOUBLE VEHICLE CROSSING DETAIL NOT TO SCALE

DATE DRN. APP. REV




MASS ROCK RETAINING WALL FOOTING DETAIL PARALLEL WITH SEWER MAIN (MAX. 600mm HEIGHT) NTS






SCALE 1:10



600 WIDE INVERT CHANNEL (600 INV) DETAIL SCALE 1:10



400x75x10 PL CLEAT (GALV) -

6CFW TO SOLDIER 2M16

BOLTS TO FENCE POSTS


50x50x5 GALV PL WASHERS.


LOTS FINISHED SURFACE

300mm WIDE -

CONCRETE SLEEPER RETAINING WALL SCHEDULE						
HEIGHT - H(mm) DEPTH - D(mm) SOLDIERS SIZE @ 2.4m CTS						
600	900	100 UC 14.8				
800	1200	100 UC 14.8				
1000	1500	100 UC 14.8				

Dmin TO BE GREATER OF THAT SHOWN ABOVE OR 1000mm BELOW ADJACENT SEWER / FRAINAGE





ISSUED FOR CONSTRUCTION

Beveridge Williams & Co. Pty Ltd has granted a licence to the principle to use this document for its intended purpose. No unauthorised copying is permitted PROPERTY GROU A ISSUED FOR CONSTRUCTION 21.12.22 C.D M.F

DESCRIPTION

DATE DRN. APP





Designed Date	C.DAWSON 28.09.2022
Drawn	L.SUTHERLAND
Approved Date	M.FELICIANO 18.11.2022

PS Number PS904418Y




Project Details	MERIDIAN CENTRAL ESTATE STAGE 40 CITY OF CASEY
Drawing Title	RETAINING WALL DETAILS

AND GENERAL DETAILS

Sheet	03 of	17	
Scale			
AS SHO	ΝN		
/ (0 01101	· • • • • • • • • • • • • • • • • • • •		
Project Ref	Stage No	Drawing No	Rev
1801767	40	003	Α

K:\Jobs Data\1801767 - Meridian_Eng\Stage 40\Drawings\1801767-40-002-DET.dwg



Road Name	Reserve		Road Width (n	n)	Kerb	Type	Verge W	Vidth (m)
Road Name	Width (m)	Lip to Lip	Inv to Inv	Back to Back	Nth/West	Sth/East	Nth/West	Sth/East
BERRENDA STREET (E-W)	14.50	6.40	7.30	7.60	600 B2	600 B2	2.70	4.50
BERRENDA STREET (N-S)	16.00	6.40	7.30	7.60	600 B2	600 B2	4.20	4.50
KHILLARI CIRCUIT (LOTS 4020 - 4022)	16.00	6.40	7.30	7.60	600 B2	600 B2	4.50	4.20
KHILLARI CIRCUIT (LOTS 4023 - 4028)	14.50	6.40	7.30	7.60	600 B2	600 B2	4.50	2.70
AWEIL LANE	8.00	5.60	-	6.20	300 ES	300 ES	0.90	0.90

	G	ias	ND -	Water	Wa	ater	Elec	tricity	Telecomn	nunication	Sewer		
Location	Side	Offset (m)	Side	Offset (m)	Side	Offset (m)	Side	Offset (m)	Side	Offset (m)	Side	Offset (m)	
BERRENDA STREET (14.50m)	S	2.10	S	2.50	S	2.95	N	1.10	N	0.40	-	-	
BERRENDA STREET (16.00m)	Е	2.10	Е	2.50	Е	2.95	W	2.60	W	1.90	-	-	
KHILLARI CIRCUIT (LOTS 4020 - 4022)	N	2.10	N	2.50	N	2.95	S	2.60	S	1.90	N	Ex1.0	
KHILLARI CIRCUIT (LOTS 4023 - 4028)	N	2.10	N	2.50	N	2.95	S	1.15	S	0.45	-	-	
AWEIL LANE	-	-	-	-	-	-	-	-	-	-	S	2.00	

0 5 10 20 30 40 SCALE 1:500 AT A1 SIZE WARNING
BEWARE OF UNDERGROUND SERVICES

The locations of underground services are approximate only and their exact position should be proven on site.

No guarantee is given that all existing services are shown.

Locate all underground services before commencement of works

DIAL 1100 BEFORE YOU DIG

www.1100.com.au

LEGEND - LAYOUT PLAN

SWALE DRAIN

− − −H HOUSE DRAIN

— OPTIC FIBRE

— G — GAS — DW — WATER

——GW—— SERVICE CONDUITS

STORMWATER DRAIN, PIT & PROPERTY INLET

MELBOURNE WATER DRAIN & PIT

S SEWER & MAINTENANCE STRUCTURES

TACTILE PAVERS (INDICATIVE ONLY)

—— EXE —— EXISTING ELECTRICITY (UNDERGROUND)

——EXO/H E—— EXISTING ELECTRICITY (OVERHEAD)

--- EXISTING TELECOMMUNICATIONS

— EXNOW — EXISTING RECYCLED WATER

EXISTING STORMWATER DRAIN

EXISTING MELBOURNE WATER DRAIN

141.34 EXISTING SURFACE LEVEL

FS140.35 FINISHED BUILDING LINE LEVEL

FR157.40 FINISHED RIDGE LINE LEVEL

BW159.30 BOTTOM OF RETAINING WALL

PAVEMENT TREATMENT

EXISTING TREE TO BE REMOVED

PERMANENT SURVEY MARK

TREE PROTECTION ZONE (TPZ)

TEMPORARY BENCH MARK

STRUCTURAL FILL > 200mm DEEP

EX. STRUCTURAL FILL > 200mm DEEP

ALLOTMENT TO BE GRADED EVENLY IN DIRECTION OF FALL TO LEVELS INDICATED

CONCRETE EDGE STRIP WITH SUBSOIL DRAIN,
"NO ROAD" SIGN & BARRIER

TW159.30 TOP OF RETAINING WALL

DIRECTION OF FALL
OVERLAND FLOW

→ LIMIT OF WORKS

PROPOSED DRIVEWAY

E — ELECTRICITY (UNDERGROUND)

— O/H E — ELECTRICITY (OVERHEAD)

— T — TELECOMMUNICATIONS

— NDW — RECYCLED WATER

—— ExG —— EXISTING GAS

— EXDW — EXISTING WATER

→ Ex S — EXISTING SEWER

RIDGE LINE
RETAINING WALL
ZERO LOT LINES

—— EXO —— EXISTING OPTIC FIBRE

ISSUED FOR CONSTRUCTION

© COPYRIGHT All rights reserved
Beveridge Williams & Co. Pty Ltd has granted a licence to the principle to use this document for its intended purpose.
No unauthorised copying is permitted

A ISSUED FOR CONSTRUCTION

21.12.22 C.D M.F

REV

DESCRIPTION

DATE DRN. APP. REV

DESCRIPTION

DATE DRN. APP.









www.beveridgewilliams.com.au


Project Details	MERIDIAN CENTRAL ESTATE
	STAGE 40
	CITY OF CASEY
	CITI OF CASET


CITY OF CASEY


Drawing Title LAYOUT PLAN (SHEET 1 OF 2)


Sheet 04 of 17
Scale
1:500 @ A1
Project Ref Stage No Drawing No

K:\Jobs Data\1801767 - Meridian_Eng\Stage 40\Drawings\1801767-40-010-LAY.dwg









Project Details MERIDIAN CENTRAL ESTATE STAGE 40 CITY OF CASEY

Drawing ROAD LONGITUDINAL SECTIONS

Sheet 08 of 17 1:500 H 1:50 V @ A1 Stage No Drawing No

ISSUED FOR

CONSTRUCTION

<u>LEGEND</u>

— — — — EXISTING SURFACE DESIGN LINE


— — — — FUTURE DESIGN LINE

— · — · — · — RIGHT LIP OF KERB

—— — LEFT LIP OF KERB

EXISTING SURFACE AT RIGHT BOUNDARY

EXISTING SURFACE AT LEFT BOUNDARY



KHILLARI CIRCUIT LONGITUDINAL	SECTION (CONTINUED)

© COPYRIGHT All rights reserved Beveridge Williams & Co. Pty Ltd has granted a licence to the principle to use this document for its intended purpose. No unauthorised copying is permitted								
								DDOWN
								DROWN _
								PROPERTY GROUP
Α	ISSUED FOR CONSTRUCTION	21.12.22	C.D	M.F				

DESCRIPTION

DATE DRN. APP. REV

DESCRIPTION

MERIDIAN CENTRAL

DATE DRN. APP.


HORIZ 1:500 VERT 1:50


SCALE AT A1 SIZE

C.DAWSON 28.09.2022 Drawn L.SUTHERLAND Approved M.FELICIANO 18.11.2022 PS904418Y PS Number

KHILLARI CIRCUIT (SHEET 2 OF 2)


STRUCTURAL FILL REQUIRED UNDER PAVEMENT AND FOOTPATHS WHERE CONSTRUCTED ABOVE NATURAL SURFACE. REFER GEOTECH REPORT FOR SPECIFICATION







CH 10.000

OFFSET









TPCH 18.351

AWEIL LANE CROSS SECTIONS BERRENDA STREET CROSS SECTIONS


> ISSUED FOR CONSTRUCTION


										CONCINCOTION
© COPYRIGHT All rights reserved Beveridge Williams & Co. Pty Ltd has granted a licence to the principle to use this document for its intended purpose. No unauthorised copying is permitted						 esigned ate	C.DAWSON 28.09.2022	Beveridge Williams	Project Details MERIDIAN CENTRAL ESTATE STAGE 40	Sheet 09 of 17
		BROWN PROPERTY GROUP MERIDIAN	HORIZ. 1:100 VERT. 1:50	0 1	1 2		SUTHERLAND M.FELICIANO	1 Glenferrie Road Malvern VIC 3144	CITY OF CASEY Drawing Title ROAD CROSS SECTIONS	1:100 H 1:50 V @ A1
A ISSUED FOR CONSTRUCTION 21.12.22 C.D M.F REV DESCRIPTION DATE DRN. APP	DESCRIPTION DATE DRN. A	P. CENTRAL			SCALE AT A1 SIZE	ate S Number	18.11.2022 PS904418Y	ph: 03 9524 8888 www.beveridgewilliams.com.au	AWEIL LANE AND BERRENDA STREET	Project Ref Stage No Drawing No Rev 1801767 40 200 A
										K:\Jobs Data\1801767 - Meridian_Eng\Stage 40\Drawings\1801767-40-200-RXS.c






STRUCTURAL FILL REQUIRED UNDER PAVEMENT AND FOOTPATHS WHERE CONSTRUCTED ABOVE NATURAL SURFACE. REFER GEOTECH REPORT FOR SPECIFICATION






TPCH 382.627



TPCH 359.027




CH 327.227

ISSUED FOR CONSTRUCTION

	YRIGHT All rights reserved								
Beverid	ge Williams & Co. Pty Ltd has granted a licence to the principle to use this docume	ent for its inter	ided pur	pose.					
ino unat	uthorised copying is permitted								
Α	ISSUED FOR CONSTRUCTION	21.12.22	C.D	M.F					
REV	DESCRIPTION	DATE	DRN.	APP.	REV	DESCRIPTION	DATE	DRN.	APP.












Project Details	MERIDIAN CENTRAL ESTATE STAGE 40 CITY OF CASEY

wing	ROAD CROSS SECTIONS
	KHILLARI CIRCUIT
	(SHEET 2 OF 2)

Sheet	12 of	17					
1:100 H 1:50 V @ A1							
Project Ref	Stage No	Drawing No	Re				
1801767	40	203	1				

K:\Jobs Data\1801767 - Meridian_Eng\Stage 40\Drawings\1801767-40-200-RXS.dwg




LIP LINE XX

 Point no
 Easting
 Northing
 RL

 XX1
 2443.820
 281.178
 42.572

 XX2
 2453.421
 288.644
 42.792

Curve no I Radius Arc A B X Y I Mid point RL XX1 - XX2 90.000 8.600 13.509 2.519 1.864 3.291 2.790 3.377 42.673




LIP LINE YY


 Point no
 Easting
 Northing
 RL


 YY1
 2459.771
 287.849
 42.792

 YY2
 2467.237
 278.248
 42.679

Curve no I Radius Arc A B X Y I Mid point RL YY1 - YY2 90.000 8.600 13.509 2.519 1.864 3.291 2.790 3.377 42.736








ISSUED FOR CONSTRUCTION

Beveridge Williams & Co. Pty Ltd has granted a licence to the principle to use this document for its intended purpose. No unauthorised copying is permitted A ISSUED FOR CONSTRUCTION 21.12.22 C.D M.F DATE DRN. APP. REV DATE DRN. APP.







C.DAWSON 28.09.2022 Drawn L.SUTHERLAND Approved M.FELICIANO 18.11.2022 PS904418Y PS Number




Project Details MERIDIAN CENTRAL ESTATE STAGE 40 CITY OF CASEY Drawing INTERSECTION DETAILS

Sheet 13 of 17

1:200 H 1:20 V @ A1 Stage No Drawing No

K:\Jobs Data\1801767 - Meridian_Eng\Stage 40\Drawings\1801767-40-300-INT.dwg



DENOTES 20mm CLASS 3 FCR BACKFILL. BERRENDA STREET INVERT LEVEL SOURCED FROM BEVERIDGE WILLIAMS INVERT LEVEL SOURCED FROM BEVERIDGE WILLIAMS DESIGN PLANS DESIGN PLANS DWG No. 1801767-39 REV P1 DWG No. 1801767-37 REV P1 INVERT LEVEL SOURCED FROM BEVERIDGE WILLIAMS DESIGN PLANS DWG No. 1801767-39 REV P1 CRB CRB DESIGN FLOW (m3/s) CAPACITY (m3/s) AT GRADE VELOCITY (m/s) PIPE SIZE (mm) _____ 375Ø 375Ø = 300Ø > PIPE GRADE DATUM DEPTH TO INVERT H.G.L INVERT LEVEL FINISHED SURFACE EXISTING SURFACE PIPE CHAINAGE (Reach Length) ISSUED FOR CONSTRUCTION © COPYRIGHT All rights reserved

Beveridge Williams & Co. Pty Ltd has granted a licence to the principle to use this document for its intended purpose.

No unauthorised copying is permitted Project Details MERIDIAN CENTRAL ESTATE C.DAWSON Sheet 15 of 17 Beveridge Williams 28.09.2022 STAGE 40 CITY OF CASEY Drawn L.SUTHERLAND HORIZ 1:500 1:500 H 1:50 V @ A1 1 Glenferrie Road Drawing Title DRAINAGE LONGITUDINAL SECTIONS MERIDIAN CENTRAL Approved M.FELICIANO

SCALE AT A1 SIZE

A ISSUED FOR CONSTRUCTION

21.12.22 C.D M.F

DATE DRN. APP. REV

DESCRIPTION

DATE DRN. APP

Malvern VIC 3144

ph: 03 9524 8888

www.beveridgewilliams.com.au

(SHEET 1 OF 2)

18.11.2022

PS904418Y

PS Number

NOTES:
ALL STORMWATER DRAINS UP TO AND

INCLUDING 750mm DIA. ARE TO BE CLASS 2

R.R.J. PIPES UNLESS NOTED OTHERWISE.

— — — EXISTING SURFACE

— DESIGN SURFACE

DRAINAGE PIPE/PIT — — EXISTING DRAINAGE PIPE/PIT — HYDRAULIC GRADE LINE

Stage No Drawing No


K:\Jobs Data\1801767 - Meridian_Eng\Stage 40\Drawings\1801767-40-400-DLS.dwg

NOTES:
ALL STORMWATER DRAINS UP TO AND INCLUDING 750mm DIA. ARE TO BE CLASS 2 R.R.J. PIPES UNLESS NOTED OTHERWISE.

LEGEND

— — — EXISTING SURFACE
DESIGN SURFACE
DRAINAGE PIPE/PIT
HYDRAULIC GRADE LINE

DENOTES 20mm CLASS 3 FCR BACKFILL.




ISSUED FOR CONSTRUCTION

© COP	YRIGHT All rights reserved								
Beveride	ge Williams & Co. Pty Ltd has granted a licence to the principle to use this docume	ent for its inter	ided pur	pose.					
No unau	uthorised copying is permitted								
Α	ISSUED FOR CONSTRUCTION	21.12.22	C.D	M.F					
REV	DESCRIPTION	DATE	DRN.	APP.	REV	DESCRIPTION	DATE	DRN.	AP

BROWN PROPERTY GROUP





Designed C.DAWSON Date 28.09.2022

Drawn L.SUTHERLAND

Approved M.FELICIANO Date 18.11.2022

PS Number PS904418Y



Project Details	MERIDIAN CENTRAL ESTATE
	STAGE 40
	CITY OF CASEY
	CITI OF CASET

rawing tle	DRAINAGE LONGITUDINAL SECTIONS
	(SHEET 2 OF 2)

Sheet	17		
Scale 1:500 H 1	l:50 V	@ A1	
Project Ref	Stage No	Drawing No	Rev
1801767	40	401	Α

K:\Jobs Data\1801767 - Meridian_Eng\Stage 40\Drawings\1801767-40-400-DLS.dwg

PIT SCHEDULE											
PIT	PIT TYPE	INTE	INTERNAL		INLET		OUTLET		Г		
NAME		WIDTH	LENGTH	DIA	INV LEV	DIA	INV LEV	SETOUT RL	DEPTH	STD DWG	REMARKS
Ex.9	END PIPE			375	40.535	375	40.535	42.563	2.028		CONNECT TO EXISTING END PIPE
10	GRATED ENTRY PIT	600	900	375	40.938	375	40.888	42.699	1.810	EDCM 601 & 605	
11	GRATED ENTRY PIT	600	900	300	41.178	375	41.103	42.925	1.822	EDCM 601 & 605	
				300	41.178						
12	GRATED ENTRY PIT	600	900	300	41.313	300	41.263	42.925	1.662	EDCM 601 & 605	
13	GRATED ENTRY PIT	600	900	300	43.184	300	43.134	44.602	1.468	EDCM 601 & 605	
Ex.E.P8	END PIPE					300	43.369	44.805	1.436		CONNECT TO EXISTING END PIPE
76	JUNCTION PIT	600	900	225	43.285	225	43.235	44.716	1.482	EDCM 605	CONSTRUCT NEW PIT AT EXISTING END PIPE
77	JUNCTION PIT	600	900			225	44.033	44.855	0.822	EDCM 605	
79	GRATED ENTRY PIT	600	900			300	43.017	44.635	1.618	EDCM 601 & 605	
Ex.82	END PIPE			375	39.093	375	39.093	40.685	1.592		CONNECT TO EXISTING END PIPE
83	GRATED ENTRY PIT	600	900	300	39.838	375	39.763	41.346	1.583	EDCM 601 & 605	
				300	39.838						
84	JUNCTION PIT	600	900	300	40.208	300	40.158	41.878	1.720	EDCM 605	
				225	40.233						
Ex.92	END PIPE			225	41.167	225	41.167	42.152	0.985		CONNECT TO EXISTING END PIPE
93	JUNCTION PIT	600	900			225	41.467	42.294	0.827	EDCM 605	
94	GRATED ENTRY PIT	600	900			300	39.98	41.352	1.372	EDCM 601 & 605	
95	JUNCTION PIT	600	900			225	41.693	42.579	0.885	EDCM 605	

ISSUED FOR CONSTRUCTION

© COPYRIGHT All rights reserved
Beveridge Williams & Co. Pty Ltd has granted a licence to the principle to use this document for its intended purpose.
No unauthorised copying is permitted

A ISSUED FOR CONSTRUCTION

21.12.22 C.D M.F

REV

DESCRIPTION


DATE DRN. APP. REV

DESCRIPTION

DATE DRN. APP. REV







Designed Date	C.DAWSON 28.09.2022	
Drawn	L.SUTHERLAND	
Approved Date	M.FELICIANO 18.11.2022	
PS Number	PS904418Y	



	Project Details	MERIDIAN CENTRAL ESTATE STAGE 40 CITY OF CASEY	Sheet 17 of 17	
•			Scale 1:500 H 1:50 V @ A1]
	Drawing Title	PIT SCHEDULE		\perp
	Title		Project Ref Stage No Drawing No	
			1801767 40 402	

K:\Jobs Data\1801767 - Meridian_Eng\Stage 40\Drawings\1801767-40-400-DLS.dwg